ROTH RMT Certified Installer Training



ROTH RMT Certified Installer Training Objectives

- Differentiate the Roth tank, manufacturing process and features from other poly tanks
- Inform installers on the proper methods by which to configure and plumb Roth tanks
- Train installers on the importance of installation, different techniques, materials and DO's and DON'Ts of a proper installation
- Answer questions, objections, and perceptions regarding Roth poly tanks





- Extrusion descends from tooling
- Air is blown into the hot extrusion to keep it open
- Wall thickness is computer controlled to accommodate stretch and desired material distribution throughout vessel





- Sideview of machine
- Note mold change in upper left hand corner of slide
- 345 tons of materials, mechanical equipment and controls used to build machine
- •1000 pound shot largest in the world by over 250 pounds





- Material handling system
- Pneumatic conveyance of resin to blending system
- State of the art process and controls
- No air, water or solid waste discharge as a result of the process





- Post mold fixturing of tanks
- Shapes tank during final cooling
- Minimizes differential shrinkage
- Simulates compacted backfill purpose along sidewalls
- Note arched roof





FAILURE TO INSTALL TANK PROPERLY WILL VOID THE WARRANTY

* DO NOT FILL TANK WITH WATER BEFORE BACKFILL

* BED TANK ON COMPACTED BASE

* SUPPORT HAUNCH WITH GRANULAR MATERIAL (SAND, GRAVEL, PEA STONE OR SIMILAR)

* COMPACT BACKFILL IN 6" LIFTS

* DO NOT BACKFILL WITH ANY CLAY CALL FACTORY AT 866.943.7256 WITH QUESTIONS

- Warning sticker placed on every single tank at inlet end
- Empty tank
- Set on compacted bed
- Support haunches
- Compact backfill
- EMPTY, BED, HAUNCH, COMPACT
- No clay!





- A standard 5" hole saw is used for cutting inlet and outlet ports
- FL and OR tanks are predrilled at factory
- All states and provinces use A dimples except NE, IL and AZ
- Use ONLY a hole saw
- No sawzalls!





- Proper grommet installation
- Note that grommet is flat against tank
- Use non-petroleum lubricant to stab pipe into grommet (dish soap works well)
- Work pipe in at an angle and bevel if desired
- Do not attempt to stab pipe straight in





- Add bedding material to excavation and spread evenly
- Sand, fine gravel, stone dust, and other fine materials make ideal bedding
- Native material (if used) must be carefully worked, leveled and compacted
- DO NOT belly out excavation by over-digging





- Ideal bed prepared for tank
- Note uniform distribution of material
- The compacted bed supports the belly of the tank, particularly when it is filled with water
- A poorly prepared bed will allow to belly of the tank to sag and the roof to squat causing riser/lid lean





- Gravel is added along the tank sidewalls
- Note the gravel under the haunch of the tank, cradling the tank in the excavation
- Rod in material with shovels, shovel handles, etc., to ensure support of the haunch
- Sand is best "floated" or washed in with water if possible





- After getting material under the haunch of the tank, begin backfilling along sidewalls
- Level and compact material in 6" lifts as you go
- Mechanical compactors are ideal for most materials
- Failure to compact will allow excessive expansion of sidewalls





- Note that this placement of material fills all corrugations and voids
- Continue to spread material evenly, compacting as you go
- Compaction of sidewall backfill in particular provides the structural support the tank requires to maintain proper shape





• Mechanical compactors such as this plate tamper pose no threat of damage to the tank

 Review the soil compaction handbook referenced on page 5 to best determine what type of compactor is best suited to the backfill materials at each site





- Note the uniform and level placement of compacted material around the entire tank
- Note the use of all imported material to replace the heavier clayey soils encountered on this site





- Native material appropriate for backfill
- Note the relative absence of clay and the free-flowing nature of the excavated materials
- Native material such as this MUST be compacted and will (in general) be more work than importing material





- Proper compaction of previously shown native material
- Note the compaction of material all the way to the shoulders of the tank
- No further compaction of material is required at this point
- Take care in evenly backfilling around pipes and risers





- Continue backfilling over top of tank uniformly and evenly
- Hand work backfill around pipes and risers
- Note the placement of gravel around the riser in the bottom of the photo
- Uneven backfilling around risers will cause them to be out of round





- HEAVY CLAY!!!
- Do not use this to backfill tank
- Use of clay to backfill voids all warranties





- Grade evenly over tank
- Mound up over tank to allow settling and redirect runoff water
- When grading, consider roof drains, hills and other sources of surface water that should be directed AWAY from the tank





- Note the use of gravel under the effluent pipe to provide support and minimize settling
- Hand place material as necessary to provide uniform backfill





- Proper position of inlet T baffle
- Note that the sweep of the inlet T baffle allows a clearance for the riser or lid without hitting the inlet pipe
- Use ONLY factory provided plumbing or you will experience an interference fit
- If a riser is used, it may be notched to provide clearance





- Risers must be gasketed and sealed to prevent infiltration of surface/groundwater
- Surfaces must be clean and dry when applying gasketing material





- Take care to thread risers in to tank and each other as tightly as possible
- After gasket material has been installed, additional sealing may be provided using ADH 100 and/or butyl mastic
- Where the threat of severe infiltration is present, contact factory for additional instructions

Details Provided by APPIAN Consulting Engineers - www.appianengineers.com

12/06/2005 - 10:07:05 AM









- For deep bury applications (verify if allowed with local Codes) additional internal struts may be installed
- Note the PVC support pipe visible in the lower manway
- Install Schedule 40, 4" PVC pipe at each end of tank between roof and floor





- Pipe mounting brackets are molded into the floor and roof of every tank
- Tank MUST be installed exactly to installation instructions or severe damage to the tank may occur due to point loading
- Field measure each support pipe
- Proper length is 42 5/8 42 ³/₄"

ROTH RMT Certified Installer Training Questions and Answers

